M JENKINS CONSTRUCTION LTD

QUOTATION FOR ELECTRICAL WORKS

127 Tamworth Road
Woodend
Atherstone
CV9 2QQ

Kate Clover
Parish Clerk
Water Orton Parish Council
42 Elm Tree Close
Kingsbury
B78 2JG

14th March 2023

Dear Kate,

Following your instruction there has been a number of additional electrical works requested.

- 2 x 1 Kw panel heaters, one in the male and one in the female toilets. £ 485.00 This includes labour and materials. The existing lobby area heater as quoted is been relocated within the disabled toilet now. The panel heaters will provide frost protection to the surface pipework within the toilet areas.
- The smoke alarm circuit - provide 1 smoke alarm in each of the toilets, 1 smoke alarm in the lobby area, 1 heat alarm in the kitchen area, 1 x smoke alarm in the main existing building. The price to complete this element is £ 590.00
- Provide 1 x 16amp water heater circuit, installation of surface mounted switched fuse spur next to the cylinder £ 235.00
- There was an additional emergency light required in the main existing room which had not been specified into the tender questions £ 95.00.

Please note all prices exclude Vat.

Yours sincerely

M Jenkins